Checkout and Launch Control System (CLCS) Juno Delivery System Test Procedures Document

April 14, 1997

Prepared By:

CLCS System Test Team
CLCS Technical Integration
DE-CLC
Kennedy Space Center, FL 32899

Checkout and Launch Control System (CLCS) Juno Delivery System Test Procedures Document

| Prepared By: | |
|----------------------------|----------------------------------|
| David Reinhardt, | Timothy McKelvey, |
| System Test Engineer | System Test Engineer |
| Approved By: | |
| Arnold Postell, | Kirk Lougheed, |
| Technical Integration Lead | System Engineering and Technical |
| | Integration Lead |

Table of Contents

| 1.0 SCOPE | 1-1 |
|--|------|
| 1.1 Identification | 1-1 |
| 1.2 Purpose | |
| 1.3 System Overview | |
| 1.4 HARDWARE AND SOFTWARE CONFIGURATIONS | 1-2 |
| 1.5 DOCUMENT ORGANIZATION | 1-4 |
| 2.0 APPLICABLE DOCUMENTATION | 2-1 |
| 2.1 PARENT DOCUMENTS | 2-1 |
| 2.2 APPLICABLE DOCUMENTS | 2-1 |
| 2.3 REFERENCE DOCUMENTS | 2-2 |
| 3.0 TEST CASE DESCRIPTION | 3-1 |
| 3.1 System Integration Build and Configuration Management | 3-1 |
| 3.1.1 Test Description | 3-1 |
| 3.1.2 Pass/Fail Criteria | 3-2 |
| 3.1.3 Procedure | |
| 3.2 SYSTEM START-UP AND SDE CONSOLIDATED DATA FLOW | 3-9 |
| 3.2.1 Test Description | |
| 3.2.2 Pass/Fail Criteria | 3-10 |
| 3.2.3 Procedure | |
| 3.3 TEST CASE 3.3 - LCC-X CONSOLIDATED DATA FLOW | |
| 3.3.1 Test Description | |
| 3.3.2 Pass/Fail Criteria | |
| 3.3.3 Procedure | |
| 3.4 TEST CASE 3.4 - SYSTEM OPERATIONS AND BASIC SERVICES | |
| 3.4.1 Test Description | |
| 3.4.2 Pass/Fail Criteria | |
| 3.4.3 Procedure | 3-27 |
| APPENDIX A - ACRONYMS AND DEFINITIONS | A-1 |
| APPENDIX B - REQUIREMENTS TRACEABILITY AND TEST METHODS MATRIX | B-1 |
| APPENDIX C - RESOURCE REQUIREMENTS | C-1 |
| APPENDIX D - STANDARD TEST OPERATING PROCEDURES | D-1 |

1.0 Scope

This document defines the test approach and procedures to be executed for the Juno delivery by CLCS System Engineering and Technical Integration. For the Juno delivery, testing will occur at Kennedy Space Center in the Engineering Development Laboratory (EDL) Satellite Development Environment (SDE) as well as in the Launch Control Center LCC-X demonstration facility.

1.1 Identification

This document is the Checkout and Launch Control System (CLCS) Juno Delivery System Test Procedures Document, Rev. BASIC.

1.2 Purpose

The purpose of this document is to define a suite of test procedures that will accurately assess the delivered hardware and software to ensure it is functional and meets project commitments for the Juno delivery. This Juno delivery System Test will not result in formal "buy-off" of any requirements, therefore Quality Assurance sign-off is not required. This test will act as a path finder to ensure that the CLCS delivery process is understood and complete. Formal system testing will begin with the Redstone Delivery currently scheduled for September, 1997.

1.3 System Overview

The CLCS is composed of a Real Time Processing System (RTPS) and a support system called the Shuttle Data Center (SDC). The RTPS provides the capability to checkout and control the elements of the current Space Transportation System (STS) and Ground Support Equipment (GSE). It provides support to the Space Shuttle Program into the 21st Century and a basic infrastructure upon which to base future design projects such as the Orbiter Upgrades and RLV.

The CLCS replaces the current Launch Processing System (LPS) with state-of-the-art Commercial Off the Shelf (COTS) based technology. Wherever possible, COTS software is used instead of developing software where the requirements of the task are satisfied by the COTS software products. Any developed software will be written in high level languages that have demonstrated a high degree of portability between platforms. COTS hardware is also utilized as much as possible in the CLCS. This strategy provides a highly reliable system that is both supportable, with minimal software and hardware upgrade impacts, and expandable, with a solid base design.

1.4 Hardware and Software Configurations

Figure 1 shows the Juno hardware configuration for the LCC-X demonstration facility. Figure 2 shows the Juno hardware configuration for the Satellite Development Environment 1 (SDE1) in the EDL. This test will utilize a portion of each of these environments. Specific equipment to be used will be documented in the test procedures at test time.

Figure 3 shows the Juno software configuration in the SDE1. Not all of the software in SDE1 is included in the Juno baseline. See Table 1 for a listing of the baselined software. Figure 4 shows the software configuration in the LCC-X demonstration facility. The LCC-X demonstration facility is not intended to be part of the baselined CLCS, therefore the configuration will vary depending on planned demonstrations (e.g., new versions of CLCS S/W, new HCI technology, new COTS capabilities). For the Juno System Test, the LCC-X software will be configured similarly to the SDE1 (given the differences in H/W availability)




Figure 1: LCC-X Hardware Configuration DRAWING NOT CORRECT YET






Figure 2: Satelite Development Environment - SDE1 (Shaded areas indicate equipment required for System Test)

Figure 3: SDE1 Software configuration <TBS>

Figure 4: LCC-X Software configuration <TBS>

| Software | Vendor | Version | Platform | Facility |
|------------------------------|--|---------|-----------------------------|---------------|
| IRIX (UNIX | Silicon Graphics | 6.2 | SGI Indigo 2, | SDE, |
| operating system) | Incorporated (SGI) | | SGI Indy, SGI Challenge | LCC-X |
| IRIX (UNIX operating system) | Silicon Graphics Incorporated (SGI) | 6.3 | SGI O2 | SDE, LCC-X |
| VxWorks (Gateway OS) | VxWorks | 5.2 | SDS Gateway, CS Gateways | SDE, LCC-X |
| | | | | |
| | | | | |
| | | | | |

Table 1.1: Juno Baselined COTS Software

| Software Module | CSCI | Version | Platform | Facility |
|-----------------|------|---------|---------------|----------|
| | | | SGI Indigo 2, | SDE, |
| | | | SGI Indy, | LCC-X |
| | | | SGI Challenge | |
| | | | SGI O2 | SDE, |
| | | | | LCC-X |
| | | | SDS Gateway, | SDE, |
| | | | CS Gateways | LCC-X |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Table 1.2: Juno Baselined Custom Software

1.5 Document Organization

This document is divided into three sections and four appendices:

Section 1, Scope, discusses the purpose of the CLCS System Test, provides a system overview, and describes software and hardware configurations for the system.

Section 2, Applicable Documents, lists the documents used to create and those supporting this document.

84K00XXX Rev. BASIC

Section 3, Test Case Description, contains a description of the test cases, the pass/fail criteria, and the procedures in detail.

Appendix A, Acronyms and Definitions, contains a listing of acronyms and selected word definitions (for words which may have multiple interpretations)

Appendix B, Requirements Traceability and Test Methods Matrix, contains the requirements verification matrix for the test.

Appendix C, Resource Requirements, contains a list of software, hardware, and personnel requirements necessary for each test.

Appendix D, Standard Operating Test Procedures, contains any specific, standard procedures identified within the test cases.

2.0 **Applicable Documentation**

The following documents, of the revision shown, form a part of this document to the extent specified.

2.1 Parent Documents

The documents in this paragraph establish the criteria and technical basis for the existence of this document. The parent documents are:

| Parent Document | Document | Rev. | Date |
|---|------------------|-------|---------|
| | Number | | |
| CLCS System Test Plan | N/A ¹ | BASIC | 3/27/97 |
| CLCS Program Management Plan | N/P^2 | = | - |
| CLCS System Engineering Management Plan (SEMP) | N/P | - | - |
| CLCS Project Plan | N/P | - | - |

Table 2.1: Parent Documents

2.2 Applicable Documents

Applicable documents are those documents which form a part of this document. These documents, at the revisions listed below, carry the same weight as if they were stated within the body of this document.

| Applicable Document | Document Number | Rev. | Date |
|----------------------------------|--------------------|------|------|
| CLCS System Level Specification | N/P | - | - |
| CLCS CM Plan | N/P | - | - |
| CLCS Integration Management Plan | N/P | - | - |

Table 2.2: Applicable Documents

¹ N/A indicates document number is not available. The configuration management process for CLCS program documents has not been finalized, however this document is considered baselined. 2 N/P indicates that the document has not yet been published. References are included in these tables to

show current expectations.

2.3 Reference Documents

Reference documents are those documents which, though not a part of this document, serve to clarify the intent and contents of this document.

| Reference Document | Document Number | Rev. | Date |
|--------------------------------|--------------------|------|------|
| CLCS Certification Plan | N/P | - | - |
| CLCS System Design Document | N/P | - | - |
| CLCS Software Development Plan | N/P | - | - |
| CLCS Concept of Operation | N/P | - | - |

Table 2.3: Reference Documents

3.0 Test Case Description

This section describes each test case, the expected results, the pass/fail criteria, and a step by step procedure to execute the test. Appendix B contains the Requirements Traceability and Test Methods Matrix, which maps system requirements to the test case that verifies those requirements. Test cases are stand alone, and can be executed in any order, however, it is recommended to run the test cases in the order in which they are presented.

3.1 System Integration Build and Configuration Management

The purpose of this test case is to demonstrate that the process for compiling, linking, and installing/distributing software is correct and consistent at the system level, as is the process for baseline control. These capabilities were developed in conjunction with the Juno Development Environment Foundation thread.

3.1.1 Test Description

3.1.1.1 Detailed description

Develop a short segment of code and use subsystem defined build procedures and any additional system level build procedures to take developed source code through to an operational configuration.

Verify that the software configuration control tool allows check-in and check-out of files and maintains a record of versions and changes.

3.1.1.2 Resource Requirements

3.1.1.2.1 Test Personnel

Personnel required include at a minimum a Test Conductor. Since this test will not result in formal "buy-off" of any requirements, a QA representative is not required. Skills required by test conductor (or designee) include knowledge of vendor operating procedures, including both standard user and system administrator procedures, and familiarity with software CM tools and procedures.

3.1.1.2.2 Hardware

The following hardware is required:

• Two Development workstations

3.1.1.2.3 Software

The following Software is required:

- Vendor supplied operating systems and associated utilities
- CLCS software configuration control tools (CVS)

3.1.1.2.4 Data

There are no specific data requirements for this test.

3.1.1.3 Requirements Trace

This test will simulate the demonstration of compliance with System Level Specification requirements covering the following functions:

- Create software
- Control software development
- Basic OS commands/services:
 - File copy
 - Text editing
 - Compile, make
 - Log-on, log-off

3.1.2 Pass/Fail Criteria

Successful completion of the test procedures without any problems that would result in the generation of critical PR's and without an excessive number of major PR's will be sufficient for this test to be considered passed.

3.1.3 Procedure

Refer to Procedure 3.1 in Table 3.1 for test procedures.

Procedure 3.1 - System Integration Build and Configuration Management Date: Location: Start Time:

Test Setup/Initial Conditions - This test will be executed in the SDE1. All required software and hardware will be available in the same configuration they would be if the system were to be supporting daily software development. Two workstations will be powered up and ready to accept logins for a development session.

| Step | Description | Expected Results | Comments | TC | QA |
|------|--|---|----------|----|----|
| 1. | Login as a software developer | Login is successful, initial user display is presented. | | | |
| 2. | Start the text editor vi and enter the following code: #include <stdio.h> void main(void) { printf("Hello world\n"); }</stdio.h> | Code is entered | | | |
| 3. | Save code as file "test1.c" | File is saved | | | |
| 4. | Compile code. Type: cc -o test1 test1.c | Compiles without error | | | |
| 5. | Execute program test1. Type: test1 | "Hello world" is displayed on screen | | | |
| 6. | Using the xedit editor, write a make file for test1. Type: xedit (The file should contain the following lines) test1: /test1.c <tab>cc ./test1.c -o ./test1 Save the file with the filename Makefile, quit xedit</tab> | The file "Makefile" is created. | | | |
| 7. | Delete program test1. Type: rm test1 | The file "test1" is deleted. | | | |

Table 3.1

| Step | Description | Expected Results | Comments | TC | QA |
|------------|---|---------------------------------------|----------|----|----|
| 8. | Execute the Make file. Type: | test1 compiles successfully | | | |
| | | | | | |
| | make | | | | |
| 9. | Execute program test1. Type: | "Hello world" is displayed on screen | | | |
| | test1 | | | | |
| 10. | Copy program test1 to another workstation: | The program is copied to the remote | | | |
| | | workstation | | | |
| | rcp test1 <workstation_id>:/tmp/test1</workstation_id> | | | | |
| 11. | logon to <workstation_id> and execute test1. Type:</workstation_id> | "Hello world" is displayed on screen | | | |
| | | | | | |
| | rlogin <workstation_id></workstation_id> | | | | |
| | /tmp/test1 | | | | |
| 12. | Delete the program test1 and logout of the remote | The file "/tmp/test1" is deleted and | | | |
| | workstation. Type: | the remote login session is | | | |
| | | terminated. | | | |
| | rm /tmp/test1 | | | | |
| | exit | | | | |
| 13. | Prepare the CVS/RCS repository by typing the | The SW-REPOSITORY directory is | | | |
| 100 | following commands: | created in the home directory and | | | |
| | | contains the Repository subdirectory. | | | |
| | cd ~ | | | | |
| | mkdir SW-REPOSITORY | | | | |
| | mkdir SW-REPOSITORY/Repository | | | | |
| 14. | Set up the required CVS environment variable, type | The environment variable is set. | | | |
| | (all on one line): | | | | |
| | | | | | |
| | setenv CVSROOT \$HOME/SW- | | | | |
| | REPOSITORY/Repository | | | | |

Table 3.1 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|--|---|----------|----|----|
| 15. | Initialize the repository by typing the following command: | CVS initializes without error message | | | |
| 16. | Create a local working directory and copy the files created in steps 2 and 6 into it. Also copy two of the IRIX provided C files into the local working directory. Add the copied files to the repository. Type: mkdir \$HOME/Working1 cd \$HOME/Working1 cp /usr/include/strings.h . cp /usr/include/time.h . cp/Makefile . cp/test1.c . cvs import -m "Initial entry into CVS." JunoTest CLCS Start | The files will be added to the CVS repository under the JunoTest subdirectory | | | |
| 17. | Checkout the file test1.c by typing the following command: cvs checkout JunoTest/test1.c | The file test1.c is available in the JunoTest subdirectory | | | |
| 18. | Display the status the CVS repository by using the following command: cvs status | CVS reports the initial version (1.1) of the file test1.c | | | |

Table 3.1 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|--|--|----------|----|----|
| 19. | Modify the test1.c file by adding a second printf line after the first: printf("Hello world again\n"); | The file is updated. | | | |
| | You may use vi or xedit to perform this task. The file is located in the JunoTest subdirectory (i.e. vi JunoTest/test1.c) | | | | |
| 20. | Check the modified file into CVS by using the following command (all on one line): cvs commit -m "Added a second printf." JunoTest/test1.c | CVS accepts the new version of test1.c without error | | | |
| 21. | Display the status the CVS repository using the following command: cvs status | CVS reports the new version (1.2) of test1.c | | | |
| 22. | View a log of all CVS actions to date by issuing the following command: cvs log | CVS reports logged events. | | | |
| 23. | Checkout the original version of test1.c and verify that the original copy is still in the repository by using the following commands: cvs checkout -r 1.1 JunoTest/test1.c more JunoTest/test1.c | The original version is checked out, the second printf command is shown not to be present, CVS prompts for confirmation of release | | | |
| | cvs release JunoTest (reply "y" to conformation of release) | | | | |

Table 3.1 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|--|----------|----|----|
| 24. | Delete the JunoTest subdirectory and checkout the latest version of test1.c. Verify that the latest copy is still in the repository. Type: rm -rf JunoTest cvs checkout JunoTest/test1.c more JunoTest/test1.c | The JunoTest subdirectory is deleted, then is recreated with the updated version (the second printf statement is included in the file) | | | |
| 25. | Checkout the file "Makefile" and execute the make utility. Type: cvs checkout JunoTest/Makefile cd JunoTest make | The Makefile is checked out and test1.c is compiled without error | | | |
| 26. | Execute the program test1. Type: test1 | "Hello world Hello world again" is displayed on the screen | | | |
| 27. | Release the JunoTest files checked out. Type: cd cvs release JunoTest (reply "y" to conformation of release) | CVS prompts for confirmation of release. | | | |
| 28. | Logoff of workstations. | Login session is closed, Login prompt is displayed. | | | |

Table 3.1 (cont.)

| End | Time: | |
|-----|-------|--|
| | | |

Signature Page: Test Case 3.1 - System Integration Build and Configuration Management

| <not required=""></not> | | |
|-------------------------|------|--|
| Quality Assurance | Date | |
| Test Conductor | Date | |
| Comments: | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

3.2 System Start-Up and SDE Consolidated Data Flow (Ammended)

The purpose of this test case is to demonstrate the process for taking the system from a powered off and/or quiescent state to a state in which data is flowing (end user ready to work). These capabilities were developed in conjunction with the Juno Development Environment Foundation, the Development Environment System Software, the Consolidated SDS, the Consolidated Data and the Reliable Messaging threads.

3.2.1 Test Description

3.2.1.1 Detailed description

This test follows a typical ops scenario for bringing the system up. Hardware startup, initial self test and operating system start will be demonstrated using vendor supplied procedures. Custom software that requires manual startup will then be demonstrated. Verification of successful system start will be the display of data at the HCI workstation.

3.2.1.2 Resource Requirements

3.2.1.2.1 Test Personnel

Personnel required include at a minimum a Test Conductor. Since this test will not result in formal "buy-off" of any requirements, a QA representative is not required. Skills required by test conductor (or designee) include knowledge of vendor operating procedures, including both standard user and system administrator procedures, knowledge of custom software operating procedures and familiarity with data flowing through the system.

3.2.1.2.2 Hardware

The following hardware is required:

- SDE1 networking equipment
- The SDS Gateway
- One Consolidated Systems Gateway
- The following SDE1 workstations: sde1boot, sde1net, sde1hci1, sde1hci3, sde1hci7, sde1ddp1, PCIII Support PC, PC GOAL PC

3.2.1.2.3 Software

The following Software is required:

- Vendor supplied operating systems
- All custom software that is part of the Juno delivery

3.2.1.2.4 Data

Data required for this test includes input data streams from SDS, GMS and Metro.

3.2.1.3 Requirements Trace

This test will simulate the demonstration of compliance with System Level Specification requirements covering the following functions:

- Automated system start
- System diagnostics (power-on self test)
- Transfer of data from gateways to HCI workstations
- Basic OS commands/services:
 - OS boot
 - System shutdown

3.2.2 Pass/Fail Criteria

Successful completion of the test procedures without any problems that would result in the generation of critical PR's and without an excessive number of major PR's will be sufficient for this test to be considered passed.

3.2.3 Procedure

Refer to Procedure 3.2 in Table 3.2 for test procedures.

Start Time:

Procedure 3.2 - System Start-Up and SDE Consolidated Data Flow Date:

Test Setup/Initial Conditions - This test will be executed in the SDE1 environment. All required software and hardware will be available in the same configuration they would be if the system were to have been powered down after support (e.g., for maintenance). Data sources (GMS, Metro, SDS) for the SDS gateway will be up and sending data, the SDS Gateway itself will also be up and sending data.

Location:

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|--|----------|----|----|
| 1. | Turn on SDE1 network hardware and PC's | Blinky lights start blinking on the network devices, PC's execute power | | | |
| | | on self tests, boots OS | | | |
| 2. | Turn on the sde1net workstation, wait for it to finish booting (login screen will be displayed), then turn on the sde1boot workstation and wait for it to finish booting. | POST (Power On Self Test) tests occur, Operating system start procedures initiate, Login screens appear. | | | |
| 3. | Turn on all remaining HCI workstations and the sde1ddp1 machine. | POST (Power On Self Test) tests occur, Operating system start procedures initiate, Login screens appear. | | | |
| 4. | Turn the Consolidated Systems Gateway on. | Gateway executes power on self tests, boots OS, Gateway boots in approximately 45 seconds. | | | |
| 5. | At the PCIII Support PC, enter: pcg98 | Command is accepted, the user is prompted to select a Shuttle Data Stream (SDS) | | | |
| 6. | At the PCIII Support PC, enter the number for the desired SDS. Type: | Command is accepted, data flow from the PCIII begins. | | | |

Table 3.2

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|---|----------|----|----|
| 7. | At the PC GOAL PC, start the PC GOAL software to monitor the SDS data. At the D: prompt, type: | The PC GOAL software starts and prompts user for input | | | |
| | wsm <cr> <cr></cr></cr> | | | | |
| 8. | At the PC GOAL PC, select the SDS data stream (sa083a FIFO), Type: | Command is accepted, user is prompted for input | | | |
| | Т | | | | |
| 9. | At the PC GOAL PC, select the display-build to be used. Type: | Command is accepted | | | |
| | I <cr> <cr> <cr></cr></cr></cr> | | | | |
| 10. | Login to the sde1hci7 workstation. When prompted, select the ground activity. | Login is accepted, a console window is opened, two xterm windows are opened, dnav software starts successfully. | | | |
| 11. | At the sde1hci7 workstation, telnet into the CS gateway. Type: telnet sde1csg1 | telnet connection is opened, the "->" prompt is displayed. | | | |
| 12. | Initialize the gateway ATM interface. At the "->" prompt, type: <atm "fa0:="" (wait="" assigned)<="" for="" message="" port-2="" switch="f21d0b9," th="" the=""><th>Command is accepted, messages are displayed, "->" prompt is displayed.</th><th></th><th></th><th></th></atm> | Command is accepted, messages are displayed, "->" prompt is displayed. | | | |
| | by switch") <cr></cr> | | | | |

Table 3.2 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|--|--|----------|----|----|
| 13. | Start generating data via RTCN Type : <startmet "tcid="" 'sa083a'="" (wait="" 20="" <cr="" change="" complete")="" data="" for="" input="" message="" name="" stream="" the="" to=""></startmet> | Command is accepted, messages are displayed, "->" prompt is displayed. | | | |
| 14. | Log out of the gateway. At the "->" prompt, type: | Telnet session is ended. | | | |
| 15. | Open the System messages window at the sde1hci7 workstation. In the Dnav master menu, select "System messages" | The System messages window opens and displays system messages | | | |
| 16. | Initiate data acquisition at the sde1hci7 workstation. In the Dnav master menu, select "Global Apps", then select "Start receive process", then select "GW to HCI JUNO_DDP_8" | The System messages window indicates that the Start receive process is executing, no unexpected errors are displayed in the console window. | | | |
| 17. | Start data display. In the Dnav master menu, select "Shuttle", then select any of the following: Wind Speed Wind Direction PAD A Wind Direction PAD B Temperature | The command is accepted (as shown in the System messages and console windows), the appropriate display(s) are started and are regularly updated. | | | |
| 18. | Stop data display at the workstation. Select quit from display menu(s) | Display windows are closed. | | | |
| 19. | Stop data acquisition at the workstation. In the Dnav master menu, select "Global Apps", then select "Stop receive process" | The command is accepted (as shown in the System messages and console windows), data acquisition is stopped | | | |

Table 3.2 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|--|----------|----|----|
| 20. | logout of the sde1hci7 workstation. | Logout is successful, login prompt is displayed. | | | |
| 21. | log in to each UNIX based workstation as root and issue the following command: shutdown -g0 -i0 shutdown the sde1net workstation last | Each workstation performs a clean shutdown and is ready to be powered off. | | | |
| 22. | Power off each UNIX based workstation, the PCIII support PC and the PC GOAL PC | Power is off. | | | |
| 23. | Power off the CS Gateway | Power is off. | | | |
| 24. | Power off the network equipment | Power is off, the system is in the same configuration as in the beginning of the test. | | | |
| 25. | Repeat steps 1 through 4 | Same as previous iteration. | | | |

Table 3.2 (cont.)

| End | Time: | |
|-----|-------|--|
| | | |

Signature Page: Test Case 3.2 - System Start-Up and SDE Consolidated Data Flow (Amended)

| <not required=""></not> | | |
|-------------------------|------|--|
| Quality Assurance | Date | |
| Test Conductor | Date | |
| Comments: | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

3.3 Test Case 3.3 - LCC-X Consolidated Data Flow

The purpose of this test case is to demonstrate the flow of consolidated data into the Consolidated SDS gateway, through the system to the end user display in the LCC-X environment. This test will also demonstrate system startup in the LCC-X. These capabilities were developed in conjunction with the Juno Consolidated SDS thread.

3.3.1 Test Description

3.3.1.1 Detailed description

Demonstrate the flow of consolidated data into the Consolidated gateway then through the system to the end users' display. This will be demonstrated in the LCC-X demonstration facility.

3.3.1.2 Resource Requirements

3.1.1.2.1 Test Personnel

Personnel required include at a minimum a Test Conductor. Since this test will not result in formal "buy-off" of any requirements, a QA representative is not required. Skills required by test conductor (or designee) include knowledge of vendor operating procedures, knowledge of custom software operating procedures and familiarity with data flowing through the system.

3.3.1.2.2 Hardware

The following hardware is required:

- The SDS Gateway (and associated Sun workstation)
- One Consolidated Systems Gateway
- LCC-X workstation

3.3.1.2.3 Software

The following Software is required:

- Vendor supplied operating systems
- All custom software that is part of the Juno delivery

3.3.1.2.4 Data

Data required for this test includes input data streams from SDS, GMS and Metro.

3.3.1.3 Requirements Trace

This test will simulate the demonstration of compliance with System Level Specification requirements covering the following functions:

- Automated system start
- System diagnostics (power-on self test)
- Transfer of data from gateways to HCI workstations
- Basic OS commands/services:
 - OS boot

3.3.2 Pass/Fail Criteria

Successful completion of the test procedures without any problems that would result in the generation of critical PR's and without an excessive number of major PR's will be sufficient for this test to be considered passed.

3.3.3 Procedure

Refer to Procedure 3.3 in Table 3.3 for test procedures.

Procedure 3.3 - LCC-X Consolidated Data Flow Date: Location: Start Time:

Test Setup/Initial Conditions - This test will be executed in the LCC-X demonstration facility. All required software and hardware will be available in the same configuration they would be if the system were to have been powered down after support (e.g., for

maintenance). Data sources (GMS, Metro, SDS) and the Sun workstation for the SDS gateway will be up.

| Step | Description | Expected Results | Comments | TC | QA |
|------|--|---|----------|----|----|
| 1. | Turn on LCC-X network hardware and workstations | Blinky lights start blinking on the network devices, workstations execute power on self tests, boot OS, initial login prompt appears. | | | |
| 2. | Turn the SDS Gateway and a CS gateway on and wait for the SDS GWY MAIN MENU to appear. | Gateway executes power on self tests, boots OS, SDS GWY MAIN MENU appears. | | | |
| 3. | Decide which FEPC will be used. At the SDS Gateway, select the GWY STATUS from the MAIN MENU | GWY STATUS menu item is highlighted, next menu is displayed. | | | |
| 4. | Go to RESOURCES HEALTH & STATUS and select YES | RESOURCES HEALTH & STATUS menu item is highlighted, next menu is displayed. | | | |
| 5. | Go to any of the SBCs in slot 2 through 5 and select YES, | A screen similar Screen A is displayed, the status of all SBC's will be: Health Count: 00000000 Ready: No Tables Loaded: No | | | |
| 6. | Login to the Sun workstation ("atlantis") | CDE menu appears. | | | |
| 7. | Open an X terminal window. | Xterm starts | | | |
| 8. | Telnet to the GCP using the new X terminal (NOTE: 2 gateways available: lccsdsg1 and lccsdsg2) telnet lccsdsg1 | The "GCP0>" prompt is displayed | | | |

Table 3.3

| Step | Description | Expected Results | Comments | TC | QA |
|------|--|--|----------|----|----|
| 9. | Execute the SDS initialize string . Type (all on one line): | The following messages should be displayed: | | | |
| | sdsinit "A", "2.34", "1.15", "1.16", "1.26", "A", "gms1.dat", "gms2.txt", "11", "20" | SDS init Initiated Loading and initializing FEPCA Waiting for the FEPCA to be ready SDS initialized successfully | | | |
| | | A screen similar to Screen A will be displayed on the SDS gateway. | | | |
| 10. | Logout from the GCP. Type: logout | Telnet session ends | | | |
| 12. | At the Sun workstation, telnet into the CS gateway. Type: telnet lcccsg <x></x> | telnet connection is opened, the "->" prompt is displayed. | | | |
| | where <x> is 1 or 2, depending on which gateway is used</x> | | | | |
| 13. | Initialize the gateway ATM interface. At the "->" prompt, type: | Command is accepted, messages are displayed, "->" prompt is displayed. | | | |
| | <atm "fa0:<br="" (wait="" a="" for="" message="" similar="" to="">switch=f21d0b9, port-12 assigned by switch")</atm> | | | | |

Table 3.3 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|--|--|----------|----|----|
| 14. | Start generating data via RTCN Type : <startmet "tcid="" 'sa083a'="" (wait="" 20="" <cr="" change="" complete")="" data="" for="" input="" message="" name="" stream="" the="" to=""></startmet> | Command is accepted, messages are displayed, "->" prompt is displayed. | | | |
| 15. | Log out of the gateway. At the "->" prompt, type: | Telnet session is ended. | | | |
| 16. | Logout of the Sun workstation | Login prompt appears. | | | |
| | Start HCI applications | | | | |
| 17. | Login to an HCI workstation as root | Login is successful, a console and an xterm window are started. | | | |
| 18. | In an xterm window, change current userid and set up the workstation. Type: su - demo csh cd /usr/local/gms source gms_init | Commands are accepted without error. | | | |

Table 3.3 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|--|----------|----|----|
| 19. | In the same window, remove the TCID table. If data for STS-83 is in use, Type: | The command is accepted and executed without error | | | |
| | cd /usr/people/demo/hci.sts83/fd_hci_build/Exec fd_table_remove | | | | |
| | If data for STS-84 is in use, Type: | | | | |
| | cd /usr/people/demo/hci/fd_hci_build/Exec fd_table_remove | | | | |
| 20. | In the same xterm window, build the TCID table. If data for STS-83 is in use, Type: | The table build completes without error. | | | |
| | data for 313-63 is in use, Type. | enoi. | | | |
| | fd_table_build/Static/sa083a.bsd | | | | |
| | If data for STS-84 is in use, Type: | | | | |
| | fd_table_build/Static/sa084a.bsd | | | | |
| 21. | In the same xterm window, start the receive process. | The receive process is started | | | |
| | If data for STS-83 is in use, Type: | without error. | | | |
| | cd /usr/people/demo/hci.sts83/fd_hci_recv/Exec | | | | |
| | fd_hci_recv -rm JUNO_DDP_8 | | | | |
| | If data for STS-84 is in use, Type: | | | | |
| | cd /usr/people/demo/hci/fd_hci_recv/Exec fd_hci_recv -rm JUNO_DDP_8 | | | | _ |

Table 3.3 (cont.)


| Step | Description | Expected Results | Comments | TC | QA |
|------|---|---|----------|----|----|
| 22. | In the same xterm window, start the display menu. If data for STS-83 is in use, Type: | The display menu appears | | | |
| | cd /usr/people/demo/hci.sts83/displays/Exec main-c | | | | |
| | If data for STS-84 is in use, Type: | | | | |
| | cd /usr/people/demo/hci/displays/Exec main-c | | | | |
| 23. | Start the displays. From the display menu select: | Displays are started. Data is updated periodically. | | | |
| | Monitor (then) | periodically. | | | |
| | Juno Demonstration Screens | | | | |
| | (then any of the following) | | | | |
| | ice team | | | | |
| | Relative Humidity | | | | |
| | Wind Speed | | | | |
| | Temp Wind Direction (followed by Pad A or Pad B) | | | | |
| | Shutdown Data Displays | | | 1 | |
| 24. | Stop data display at each HCI workstation: | Display is closed. | | | |
| | Select quit from display menu | | | | |

Table 3.3 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|--|--|----------|----|----|
| 25. | Shutdown SDS Gateway: | CDE menu appears. | | | |
| | Login to the Sun workstation | | | | |
| 26. | Start an X terminal from the CDE menu (if an xterm window is not already running) | xterm window opens | | | |
| 27. | Telnet to the GCP using the new X terminal (NOTE: 2 gateways available: lccsdsg1 and lccsdsg2) telnet lccsdsg1 | you should see the "GCP0>" prompt. | | | |
| 28. | Execute the SDS terminate string: sdsterm "A" | The following messages should appear: SDS term Initiated Notifying FEPCA to shutdown SDS terminated successfully | | | |
| 29. | Logout from the GCP logout | | | | |
| 30. | Logout of the Sun workstation | Login prompt appears. | | | |

Table 3.3 (cont.)

End Time: ______



Screen A

This screen shows the status of all four FEPCs. Slot 2, 3, 4, and 5. They are listed in that order. In this example the SBC in slot 2 (FEPCA) is in use.

Signature Page: Test Case 3.3 - LCC-X Consolidated Data Flow

| <not required=""></not> | | |
|-------------------------|-----------|--|
| Quality Assurance | Date Date | |
| Test Conductor | | |
| Comments: | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |

3.4 Test Case 3.4 - System Operations and Basic Services

The purpose of this test case is to demonstrate a subset of basic system services required for operating the CLCS, specifically some of the COTS services required for operating a distributed UNIX based system that have not been tested in previous test cases. These capabilities were developed in conjunction with the Juno Development Environment Foundation thread. This is not intended to be a thorough checkout of all CLCS COTS software.

3.4.1 Test Description

3.4.1.1 Detailed description

Verify the following COTS components/functions: network tools, printing, file access control.

3.4.1.2 Resource Requirements

3.4.1.2.1 Test Personnel

Personnel required include at a minimum a Test Conductor. Since this test will not result in formal "buy-off" of any requirements, a QA representative is not required. Skills required by test conductor (or designee) include knowledge of vendor operating procedures, including both standard user and system administrator procedures, knowledge of COTS software.

3.4.1.2.2 Hardware

The following hardware is required:

- Two HCI workstations connected to the ethernet portion of the development environment
- Two workstations connected to the ATM portion of the development environment

3.4.1.2.3 Software

The following Software is required:

- Vendor supplied operating systems and associated utilities
- Three user accounts, two of which are members of the same group, the third not a member of that group

3.4.1.2.4 Data

A text file called test3.4 is required.

3.4.1.3 Requirements Trace

This test will simulate the demonstration of compliance with System Level Specification requirements covering the following functions:

- Network services
- Printing
- Security (file access controls)

3.4.2 Pass/Fail Criteria

Successful completion of the test procedures without any problems that would result in the generation of critical PR's and without an excessive number of major PR's will be sufficient for this test to be considered passed.

3.4.3 Procedure

Refer to Procedure 3.4 in Table 3.4 for test procedures.

Procedure 3.4 - System Operations and Basic Services Date: Location: Start Time:

Test Setup/Initial Conditions - This test will be executed in the SDE1 environment. Workstations are available on each segment of the CLCS network and the account to be used is available on each of these workstations. The text file test3.4 is available in the home directory of the account to be used.

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|---|----------|----|----|
| | Network services | | | | |
| 1. | Log onto a development workstation connected to the ethernet portion of the CLCS network | Login is successful, initial user display is presented. | | | |
| 2. | telnet into another workstation connected to the ethernet portion of the network: telnet <workstation_id> <user_id> <password></password></user_id></workstation_id> | Remote login successful | | | |
| 3. | Verify that the file test3.4 is not present at the remote workstation or if it is , delete it: ls -al /tmp rm /tmp/test3.4 | The contents of the /tmp directory on the remote workstation is displayed | | | |
| 4. | In a second xterm window, display the contents of the file test3.4 at the local workstation: cat test3.4 | Contents of test3.4 are displayed | | | |
| 5. | From the local workstation, transfer the file test3.4 to the other workstation using ftp. Type: ftp <workstation_id> cd /tmp put test3.4 quit</workstation_id> | Transfer is successful | | | |

Table 3.4

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|---|----------|----|----|
| 6. | Display the contents of the file test3.4 at the remote workstation. Type: | Contents of test3.4 are displayed | | | |
| | cat test3.4 | | | | |
| 7. | At the local workstation, verify that the file test3.4 is not present or if it is, delete it: | The contents of the /tmp directory on the local workstation is displayed | | | |
| | ls -al /tmp rm /tmp/test3.4 | | | | |
| 8. | At the remote workstation, transfer the file test3.4 to the local workstation using rcp. Type (all on one line): | Transfer is successful | | | |
| 9. | rcp /tmp/test3.4 <local_workstation_id>:/tmp/test3.4 Display the contents of the file test3.4 at the local workstation: cat /tmp/test3.4</local_workstation_id> | Contents of test3.4 are displayed | | | |
| 10. | Repeat steps 1-9 using two workstations attached to the ATM portion of the network. Use the ATM network. | The same capabilities demonstrated on the ethernet will be available using the ATM network. | | | |
| 11. | Repeat steps 1-9 using one workstation attached to the ATM portion of the network and one workstation attached to the ethernet portion of the network. Use both network segments concurrently | The same capabilities demonstrated on the ethernet and ATM networks will be available across both (network traffic will be successfully routed from one segment to the other) | | | |
| 12. | Execute a command on a remote workstation. Type: rsh <remote_workstation_id> ps -ef</remote_workstation_id> | A list of all processes currently executing at the remote workstation will be displayed. | | | |

Table 3.4 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|--|---|----------|----|----|
| | Printing services | | | | |
| 13. | From a workstation connected to the ethernet portion of the network, print the file test3.4: | File is printed | | | |
| | lpr test3.4 | | | | |
| 14. | Print the file test3.4 to a different printer: lpr -P <pri>printer_name> test3.4</pri> | File is printed | | | |
| 15. | Log off of all workstations | Session is closed, login prompts are displayed | | | |
| | File Access Controls | | | | |
| 16. | Log into a workstation with a user id that is included in the lor_st group. Do not use the testa user id. | Login is successful, initial user display is presented. | | | |
| 17. | Create a subdirectory called test. Type: | The subdirectory test is created. | | | |
| | mkdir test | | | | |
| 18. | Change directories to test, create a short script and check the permissions on the script and directory. Type: cd test vi test4 <insert> ps -ef <escape> :wq ls -al</escape></insert> | The script test4 is created in the test directory. The owner of the test directory ("." in the ls listing) is the username entered at login time and the group of the test directory is lor_st. The permissions on the test directory are set as: drwxr-xr-x The owner of the test4 script is the username entered at login time and the group of the test directory is lor_st. The permissions on the test4 script are set as: -rw-rr | | | |

Table 3.4 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|---------------------------------------|----------|----|----|
| 19. | Attempt to execute the script test4. Type: | The script will not run, permission | | | |
| | | denied | | | |
| | test4 | | | | |
| 20. | Change the permissions on test4 and execute the | The permissions on test4 are | | | |
| | script. Type: | changed to: | | | |
| | | -rwxr-xr-x | | | |
| | chmod 755 test4 | The script executes successfully (the | | | |
| | ls -al | list of processes currently running | | | |
| | test4 | will be displayed). | | | |
| 21. | In another xterm window, change the username to | The username is changed to testa and | | | |
| | testa. The testa user id is included in the lor_st | the current working directory is the | | | |
| | group. Change directories to the test subdirectory. | test subdirectory of the home | | | |
| | Type: | directory of the username from the | | | |
| | | original login session. | | | |
| | su testa | | | | |
| | <pre><password></password></pre> | | | | |
| | whoami | | | | |
| | cd test | | | | |
| | pwd | | | | |
| 22. | Execute the script test4. Type: | The script executes successfully (the | | | |
| | | list of processes currently running | | | |
| | test4 | will be displayed). | | | |
| 23. | In the first window, change the permissions on the | The permissions on test4 are | | | |
| | test4 script and execute it. Type: | changed to: | | | |
| | | -rwxr-xr | | | |
| | chmod 754 test4 | The script executes successfully (the | | | |
| | ls -al | list of processes currently running | | | |
| | test4 | will be displayed). | | | |

Table 3.4 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|---------------------------------------|----------|----|----|
| 24. | In the second window, execute the test4 script. Type: | The script executes successfully (the | | | |
| | | list of processes currently running | | | |
| | test4 | will be displayed). | | | |
| 25. | In the first window, change the permissions on the | The permissions on test4 are | | | |
| | test4 script and execute it. Type: | changed to: | | | |
| | | -rwxrr | | | |
| | chmod 744 test4 | The script executes successfully (the | | | |
| | ls -al | list of processes currently running | | | |
| | test4 | will be displayed). | | | |
| 26. | In the second window, attempt to execute the test4 | The script will not execute, | | | |
| | script. Type: | permission denied. | | | |
| | | | | | |
| | test4 | | | | |
| 27. | In the first window, change the permissions on the | The permissions on test4 are | | | |
| | test4 script and execute it. Type: | changed to: | | | |
| | | -rwxr-xr | | | |
| | chmod 754 test4 | The script executes successfully (the | | | |
| | ls -al | list of processes currently running | | | |
| | test4 | will be displayed). | | | |
| 28. | In the second window, execute the test4 script. Type: | The script executes successfully (the | | | |
| | | list of processes currently running | | | |
| | test4 | will be displayed). | | | |

Table 3.4 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|--|----------|----|----|
| 29. | In the second window, change the username to testb. | The username is changed to testb and | | | |
| | The testb user id is not included in the lor_st group. Change directories to the test subdirectory. Type: | the current working directory is the test subdirectory of the home | | | |
| | change directories to the test subunctiony. Type: | directory of the username from the | | | |
| | exit | original login session. | | | |
| | su testb | | | | |
| | <pre><password> whoami</password></pre> | | | | |
| | cd test | | | | |
| | pwd | | | | |
| 30. | In the second window, attempt to execute the test4 | The script will not execute, | | | |
| | script. Type: | permission denied. | | | |
| | test4 | | | | |
| 31. | In the first window, change the permissions on the | The permissions on test4 are | | | |
| | test4 script and execute it. Type: | changed to: | | | |
| | chmod 755 test4 | -rwxr-xr-x The script executes successfully (the | | | |
| | ls -al | list of processes currently running | | | |
| | test4 | will be displayed). | | | |
| 32. | In the second window, execute the test4 script. Type: | The script executes successfully (the | | | |
| | | list of processes currently running | | | |
| | test4 | will be displayed). | | | |

Table 3.4 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|---------------------------------------|----------|----|----|
| 33. | In the first window, change the permissions on the | The permissions on test4 are | | | |
| | test4 script, change the group ownership to a group | changed to: | | | |
| | that the testb user id is a member of, and execute it. | -rwxr-xr | | | |
| | Type: | The group ownership of test4 is | | | |
| | | lor_cma | | | |
| | chmod 754 test4 | The script executes successfully (the | | | |
| | chgrp lor_cma test4 | list of processes currently running | | | |
| | ls -al | will be displayed). | | | |
| | test4 | | | | |
| 34. | In the second window, execute the test4 script. Type: | The script executes successfully (the | | | |
| | | list of processes currently running | | | |
| | test4 | will be displayed). | | | |
| 35. | In the second window, change the username to testa. | The username is changed to testa and | | | |
| | The testa user id is not included in the lor_cma group. | the current working directory is the | | | |
| | Change directories to the test subdirectory. Type: | test subdirectory of the home | | | |
| | | directory of the username from the | | | |
| | exit | original login session. | | | |
| | su testa | | | | |
| | <pre><password></password></pre> | | | | |
| | whoami | | | | |
| | cd test | | | | |
| | pwd | | | | |
| 36. | In the second window, attempt to execute the test4 | The script will not execute, | | | |
| | script. Change the current directory to the next | permission denied. The current | | | |
| | higher level directory. Type: | working directory is changed. | | | |
| | | | | | |
| | test4 | | | | |
| | cd | | | | |
| | pwd | | | | |

Table 3.4 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|--|---|----------|----|----|
| 37. | In the first window, change the current directory to the next higher level directory. Change the permissions on the test directory. Type: cd | The permissions on test are changed to: drwxr-xr | | | |
| | chmod 754 test ls -al | | | | |
| 38. | In the second window, list the contents of the test directory. Type: ls -al test | The contents of the test directory are displayed. | | | |
| 39. | In the second window, change the username to testb. The testb user id is not included in the lor_st group. Type: exit su testb <password> whoami pwd</password> | The username is changed to testb and the current working directory is the home directory of the username from the original login session. | | | |
| 40. | In the second window, attempt to list the contents of the test directory. Type: ls -al test | The command fails, permission denied. | | | |
| 41. | In the first window, change the permissions on the test directory. Type: chmod 755 test ls -al | The permissions on test are changed to: drwxr-xr-x | | | |

Table 3.4 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|---|----------|----|----|
| 42. | In the second window, list the contents of the test directory. Type: | The contents of the test directory are displayed. | | | |
| | ls -al test | | | | |
| 43. | In the second window, attempt to write to the test subdirectory. Type: | The command fails, permission denied. | | | |
| | cp /etc/printcap test/printcap | | | | |
| 44. | In the second window, attempt to delete the test4 script. Type: rm test/test4 (answer "y" if prompted to override mode 0754) | The command fails, permission denied. | | | |
| 45. | In the first window, change the permissions on the test directory. Type: chmod 777 test ls -al | The permissions on test are changed to: drwxrwxrwx | | | |
| 46. | In the second window, write to the test subdirectory. Type: cp /etc/printcap test/printcap ls -al test | The copy command is successful, the contents of the test directory are displayed. | | | |

Table 3.4 (cont.)

| Step | Description | Expected Results | Comments | TC | QA |
|------|---|---|----------|----|----|
| 47. | In the second window, end the testb user id session., delete the test directory and log out of the workstation. Type: | The testb session is ended, the directory is deleted, the login session is ended and the login prompt is displayed. | | | |
| | exit rm -rf test <select from="" logout="" menu="" pop-up="" the=""></select> | | | | |

Table 3.4 (cont.)

| End | Time: | |
|-----|-------|--|
| | | |

<Not required> **Quality Assurance Date Test Conductor Date Comments:**

Signature Page: Test Case 3.4 - System Operations and Basic Services

Appendix A - Acronyms and Definitions

AT Acceptance Test - Test to accept hardware and software from a vendor

Certification Final approval to use a system for a specified set of operations (e.g.,

hazardous operations in the HMF, launch operations, etc.)

CI Configuration Item
CIT CSCI Integration Test

CLCS Checkout and Launch Control System

CM Configuration Management
COTS Commercial Off The Shelf
CSC Computer Software Component

CSCI Computer Software Configuration Item

DAR Delivery Acceptance Review

EDL Engineering Development Laboratory

GSE Ground Support Equipment

HCI Human Computer Interface HMF Hypergol Maintenance Facility

HW Hardware

HWCI Hardware Configuration Item

IDE Integrated Development Environment

I/F Interface

KSC Kennedy Space Center

LAN Local Area Network
LCC Launch Control Complex

LMSMS Lockheed Martin Space Mission Systems and Services

LPS Launch Processing System

NASA National Aeronautics and Space Administration

MSC Mission Systems Contract (held by LMSMS)

OS Operating System

PTR Post-Test Review PR Problem Report

QA Quality Assurance
QE Quality Engineering
QT Qualification Test

RLV Reusable Launch Vehicle
RTPS Real Time Processing System
RVM Requirements Verification Matrix

SDC Shuttle Data Center

SDE Satellite Development Environment SEMP System Engineering Management Plan

SFOC Space Flight Operations Contract (held by USA)

ST System Test

SLWT Super Light Weight Tank

S&MA Safety and Mission Assurance (includes Reliability, Maintainability,

Safety and Quality Assurance)

STS Space Transportation System

SW Software

TC Test Conductor

TPR Test Progress Review

TR Test Report

TRR Test Readiness Review

UAT User Acceptance Test - Test performed by user community post delivery

as part of the system certification process

UIT Unit Integration Test
USA United Space Alliance

UT Unit Test

Validation Testing performed by organization(s) outside of the developing

organization to ensure that the delivered system processes data correctly

and conforms to the operations concepts

Appendix B - Requirements Traceability and Test Methods Matrix

The following table is intended to show which System Level Specification requirement is demonstrated in each CLCS System Test (at least one System Test per delivery) and what test method was used in that test case. This table will be updated and baselined with each System Test starting with the Redstone Delivery System Test.

| | | Test | Associated | | Test | Method | |
|-------------|--------|------|------------|------------|----------|---------------|------|
| Requirement | System | Case | Threads | Inspection | Analysis | Demonstration | Test |
| | Test | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Appendix C - Resource Requirements

<TBS, defines personnel requirements, hardware and software configurations, data and test tools for standardized and generic test configurations. Not needed for Juno, may or may not be needed in future System Test procedures documents>

Appendix D - Standard Test Operating Procedures

<TBS, defines frequently used test or test setup procedures. Not needed for Juno, may or may not be needed in future System Test procedures documents>